

= NR. SIMBOL ART.	CANTITATE	UM	PU MAT	VAL MAT	=
= D E N U M I R E			PU MAN	VAL MAN	=
=	A R T I C O L		PU UTI	VAL UTI	=
=			PU TRA	VAL TRA	=
= SPOR MAT MAN UTI	GR./UA	GR.TOT.		T O T A L	=

001 M1M05A1 M 70.000  
 DEMONTAR CONDUCTEI DIN OL MONTATA IN  
 CANAL LA 1M ADINCIME SAU SUPRATERAN PINA  
 LA H=3M DN=25;40;

0.000

002 SA10C1 M 32.000  
 TEAVA PVC NEPLASTIF.TIP G MONT.LA  
 CONSTR.INDUSTR. IN COLOANE D=32 MM

0.000

002 4402329 ML. 32.000  
 TEAVA PPR D= 32 MM

0.000

003 SA10B1 M 40.000  
 TEAVA PVC NEPLASTIF.TIP G MONT.LA  
 CONSTR.INDUSTR. IN COLOANE D=25 MM

0.000

003 4402327 ML. 40.000  
 TEAVA PPR D= 20 MM

0.000

004 IC54A1 BUC. 20.000  
 RACORD OLANDEZ U2 NG.FILET INTER-  
 EXTERIOR DIN FONTA MALEABILA D =3/8 TOLI

0.000

004 2354536 BUC. 20.000  
 CONECTORI PPR D=20MM (1/2")

0.000

005 IC50C1 [ 1 ] BUC. 70.000  
 COT PPR D= 20 MM

0.000

005 3357017 BUC. 70.000  
 COT PPR D=20 MM LA 90GR

0.000

006 IC34L1 [ 1 ] BUC. 20.000  
 FITINGURI DIN PPR D= 32

*Instalare coloana  
 teava tur-retur*



		0.000	
006	2354469	BUC.	20.000
TEU PPR D= 32-25-32MM			
		0.000	
007	IC3401	[ 1 ] BUC.	20.000
TEU PPR D=32 MM			
		0.000	
007	2354465	BUC.	20.000
TEU PPR 32-20-32 MM			
		0.000	
008	RPIC80A1	BUC.	12.000
INLOCUIT SAU INTERCALAT FITINGURI (COT, MUFA, TEU, NIPLU, REDUCTII) 3/8-1 "			
		0.000	
008	2354528	BUC.	12.000
MUFA PPR D= 50MM			
		0.000	
009	IC35B1	BUC.	30.000
BRATARI PT.FIXAREA TEVI.OTEL LA INST. INCALZ.SAU GAZE MONT.IN ZID.CARAM.SAU BETON D=3/8 TOLI			
		0.000	
010	IC35C1	BUC.	40.000
BRATARI PT.FIXAREA TEVI.OTEL LA INST. INCALZ.SAU GAZE MONT.IN ZID CARAM.SAU BETON D= 1/2 TOLI			
		0.000	
011	RPIC80B1	BUC.	2.000
INLOCUIT SAU INTERCALAT FITINGURI (COT, MUFA, TEU, NIPLU, REDUCTII) 1 1/2-2 1/2 "			
		0.000	
011	4122246	BUC.	2.000
RACORD OLANDEZ ETANSARE PLANA FILET INTERIOR EXTERIOR U2 S482 DN 32 11/4			
		0.001	
012	ID01A1	BUC.	20.000
ROBINET VENTIL DUBLU REGLAJ DE COLT PT. INST.INCALZIRE CENTRALA CU D: 3/8''			
		0.000	
012	4202735	BUC.	20.000
ROBINETE CU DUBLU REGLAJ PENTRU RADIATOARE 1/2 TOLI FC			
		0.001	

Cheltuieli directe din articole: